



1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	33	37	38	48	49	50	51	55
LINE	120V	NEUT	GROUND					FEED	OPEN	CLOSE	N.C.		FEED	SHOW ST	C.CUE	INBD. CUE	UP,SHLEND	FEED	UP	DOWN	FEED	OUT	DRY CIR.		CROSS CUE	START CIR.	FEED	OPEN	CLOSE	CURTAIN		
AC FEED	MOTOR	LAMP	CHANGEOVER	EXC.	HOUSE	DIMMER	STAGE	SCRN.	N.S.																							

**TM-1 CAM TIMER**

I.D.	FUNCTION	CAM FOLLOWER SETTING
TM-1	CYCLE	DROP @ 100 LIFT @ 5
TM-2	HOLD #1	DROP @ 20 LIFT @ 56
TM-3	HOLD #2	DROP @ 56 LIFT @ 85
TM-4	C.O. CLOSE @ SHOW START	DROP @ 98 LIFT @ 2
TM-5	C.O. PULSE	DROP @ 25 LIFT @ 27
TM-6	HOUSE LIGHTS	DROP @ 10 LIFT @ 15
TM-7	STAGE LIGHTS	DROP @ 10 LIFT @ 15

**CHRISTIE AM-7 AUTOMATION CHASSIS SCHEMATIC**

**KELMAR** Systems, Inc.  
284 Broadway  
Huntington Station, NY 11746  
631-421-1230

Date:	Scale:	Drawn by:	Rev:	DWG.#
4-11-02	NONE	T.A. Mohr	A	1463